

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
CORPORATION COMMISSION

OCT 20 1977

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Okeana Oil Co.

Complete Address 970 South Finance Center, Wichita, Kans.

Lease Name Barnes Well No. 1

Location S/2 - SW - SE Sec. 33 Twp. 31 Rge. 7 (E) (W) X

County Harper Total Depth 4740

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Felso Casing Pulling

Address Box 176 - Chase, Kans. 67524 License No. 683

Operation Completed: Hour 12 N Day 17 Month Oct. Year 1977

The above well was plugged as follows:

251' - 8 7/8" Casing, Cement Circ. Recovered 4210' - 4 1/2" Casing  
4 1/2" Casing set @ 4738' - 2' open hole - Cemented w/ 75-say  
Cement - Sand back to 4700' mix & dump 4' say  
Cement on top w/ Dump hauler. Set 25' rock bridge  
top @ 300' - Dump 5 yards ready mix Cement to  
top of casing.  
Ready mix - Harper Kans.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 10-20-77

INV. NO. 6057-W