


15-077-20002-00-00

Form CP-3
Rev. 6-26-62



KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
KANSAS STATE CORPORATION COMMISSION

JAN 10 1967
1-16-1967
CONSERVATION DIVISION

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address: Suite 7, 400 North Woodlawn, Wichita, Kansas

Lease Name Barnes "A" Well No. # 1

Location SE NE SE Sec. 33 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4749'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones, Inc.

Address: 830 Sutton Place, Wichita, Kansas License No. _____

Operation Completed: Hour 10:00PM Day 13th Month Jan. Year 1967

The Above well was plugged as follows:

255' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid level in the hole was at 250'. 1st cementing plug, bridged with 2 sacks of dry cement and 1/2 sack of hulls on fluid at 250', and cemented with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and cemented with 9 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-16-67

INV. NO. 4607-W

Signed: Achie Elving
Well Plugging Supervisor