

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Imperial Oil Company

Complete Address: 780 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Palmer Well No. # 1

Location C SW NW Sec. 35 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4900'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Imperial Oil Company

Address: 780 Fourth National Bank Bldg., Wichita, Kans. License No. _____

Operation Completed: Hour 1:30PM Day 1st Month July Year 1966

The Above well was plugged as follows:

243' of 8 5/8" surface pipe, cement circulated with 180 sacks. Hole was
filled with drilling mud to 230', 1st cementing plug, bridged with 1/2 sack
of hulls on fluid at 230', and cemented with 25 sacks. Hole was filled with
drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls on
fluid at 40', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 7/7/66

INV. NO. 3530-u