

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-8-69
DEC 8 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name C & G Drlg. & G. A. Reed

Complete Address 1107 Union Nat'l Bldg., Wichita, Kansas

Lease Name Huddelston Well No. 1

Location C NE SW Sec. 27 Twp. 19 Rge. (E) (W) 20

County Ree- Rush Total Depth 1428

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co Tools

Address License No.

Operation Completed: Hour 2:15P Day 4 Month 12 Year 1969

The above well was plugged as follows:

RTD 1428' 8 5/8 csg set at 349' cwc 180 sk Cmt Mat 50-50 poz 6%

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 330' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo T. Massey
Well Plugging Supervisor

DATE 12/9/69

INV. NO. 1003-W