

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1970
10-19-70
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson
 Complete Address 408 One Twenty Building Wichita, Kansas 67202
 Lease Name Bannister "B" Well No. 1
 Location 80' SW of NE SW NE Sec. 21 Twp. 19 Rge. (E) (W) 20
 County Rush Total Depth 4425
 Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
 Other well as hereafter indicated
 Plugging Contractor Co. Tools
 Address License No.
 Operation Completed: Hour 11 P Day 16 Month 10 Year 1970

The above well was plugged as follows:

RTD 4425' 8 5/8 csg set at 283' cwc 180 sk Cmt. Mat. 100 sk reg poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Manning
Well Plugging Supervisor

INVOICED

DATE 10-29-70

INV. NO. 2713-W