

P

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 165 - 20,579 - 0000 (of this well)

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1976
3-12-76
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mull Drlg. Co. & Walter Drlg. Co.
Complete Address 415 Page Ct., 200 W. Douglas, Wichita, Kansas
Lease Name Krueger-Trust Well No. 2
Location C S/2 NE SW Sec. 21 Twp. 19 Rge. (E) (W) 20
County Rush Total Depth 4408'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Slawson Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 8:30 P Day 10 Month 3 Year 1976

The above well was plugged as follows:

RTD 4408' 8 5/8 csg set 285' cwc 200 sx. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.
Heavy mud to 250' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey
Well Plugging Supervisor

INVOICED

DATE 3-12-76
INV. NO. 2887-W