

KANSAS

Form CP-3  
Rev. 6-4-68

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
MAY 22 1972  
S-22-72  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Abercrombie Drilling, Inc.Complete Address 801 Union Center Wichita, KansasLease Name Kufeld Well No. 1Location NE SE NW Sec. 3 Twp. 19 Rge. (E) (W) 20County Rush Total Depth 4310'Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated

Plugging Contractor Co Tools

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 10:30 P Day 16 Month 5 Year 1972

The above well was plugged as follows:

RTD 6 3/4 hole to 4310' 8 5/8 csg set at 276' cwc 175 sk. Cmt. Mat. Reg Poz 6 1/2 gal.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 50 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leslie M. Masse  
Well Plugging SupervisorDATE 5/25/72INV. NO. 5941-44