

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 - 1968
2-5-68
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth Nat'l Bank Bldg., Wichita, Kansas

Lease Name Bott "A" Well No. 1

Location NW SW SE Sec. 2 Twp. 19 Rge. 20 (E) (W) X

County Rush Total Depth 4294

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 5:45 P Day 1 Month 2 Year 1968

The Above well was plugged as follows:

Rtd 4294' 8 5/8 csg set at 274' cwc 160 sc. Plg, Mat. 100 sc cem. W/6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 2/5/68

INV. NO. 7204-W