

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
4-15-68  
APR 15 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Miller "O" Well No. 1

Location SE SW SW Sec. 2 Twp. 19 Rge. 20 (E)    (W) X

County Rush Total Depth 4350

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X

Other well as hereafter indicated:   

Plugging Contractor:    Co. Tools   

Address:    License No.   

Operation Completed: Hour 3 A Day 10 Month 4 Year 1968

The Above well was plugged as follows:

RTD 4350' 8 5/8 csg set at 286' cwc 160 sc. Cem. Mat. 100 sc 50-50 poz cem. W/6% gel  
Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sc cem.  
thru drill pipe. Heavy mud to 280' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 4/15/68

INV. NO. 9579-W