

CP3

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 26 1960  
1-26-60  
CONSERVATION DIVISION  
WICHITA, KANSAS

File No. \_\_\_\_\_ County: \_\_\_\_\_ Rush

Location SW SW NW Sec. 2 Twp. 19 Rge. 20 (E) (W) \_\_\_\_\_

Name of Field: \_\_\_\_\_ Total Depth: 4310

I have this date completed supervision of plugging of:

Lease Name: J. A. Bott Well No. 1

Operator's Full Name: Continental Oil Co

Complete Address: Box 161 Great Bend, Kans

Plugging Contractor: Leben Drg Co & Halliburton Cementing Co

Address: Wichita, Kans License No. \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other Well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes    No    X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 10AM Day 18 Month 1 Year 60

The above well was plugged as follows:

8 5/8" 669' circulated with cement.

Filled hole with heavy mud, set cementing plug at 600', displaced 20 sax cement through drill pipe, heavy mud to 240', set cementing plug and 20 sax cement displaced through drill pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

Cementing by Halliburton Cementing Co.

Reviewed: J. Harris Brock

Remarks: \_\_\_\_\_

Signed: E. L. Petty  
Conservation Division Agent

INVOICED

DATE 1/29/60  
INV. NO. 847-W