

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENCY'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1977
12-15-77
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 165- 20,660-0000 (of this well)

Operator's Full Name Tomlinson Oil Co., Inc.

Complete Address Suite 1030-200 W. Douglas, Wichita, Kansas

Lease Name Bott Well No. 1

Location C E/2 SW SE Sec. 2 Twp. 19 Rge. (E) (W) 20

County Rush Total Depth 4215'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B&B Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 8:30 A Day 13 Month 12 Year 1977

The above well was plugged as follows:

RTD 4215' 8 5/8 csg set 423' cwc 250 sk. Plg. Mat. 50-50 poz 2 1/2 total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 12-16-77
INV. NO. 6391-6