

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed September 5, 1967.

Operator's Full Name E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Kansas 67202

Lease Name Brown Well No. # 1

Location C NW SW Sec. 8 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4515'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: E. K. Edmiston Drilling Company, Inc.

Address: 425 First National Bank Bldg., Wichita, Ks. License No. _____

Operation Completed: Hour 3:00AM Day 14th Month Sept. Year 1967

The Above well was plugged as follows:

239' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole was filled with drilling mud to 230', 1st cementing plug, bridged with 2 sacks of dry cement and 1/2 sack of hulls on fluid at 230', and cemented with 23 sacks, with cement from 220' to 145'. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and cemented with 9 sacks, with cement from 30' to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

STATE CORPORATION COMMISSION

Signed: *Audine Elving*
Well Plugging Supervisor

INVOICED SEP 15 1967

DATE 9/15/67
CONSERVATION DIVISION
INV. NO. 6335-W Wichita, Kansas