

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Kansas

Lease Name Davis-Brown Well No. # 1

Location C NW SE Sec. 8 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4530'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: E. K. Edmiston Drilling Company, Inc.

Address: 425 First National Bank Bldg., Wichita, Kans. License No. _____

Operation Completed: Hour 5:30AM Day 29th Month June Year 1966

The Above well was plugged as follows:

244' of 8 5/8" surface pipe, cement circulated with 135 sacks. Hole
was filled with drilling mud to 240', 1st cementing plug, bridged with
1/2 sack of hulls on fluid at 240', and cemented with 25 sacks. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2
sack of hulls on fluid at 40', and cemented with 10 sacks to the base
of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED
DATE 7/1/66
INV. NO. 3495-4