

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 22 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Barbara Oil Co.

Complete Address 509 Union Center Wichita, Ks

Lease Name Ryan-Drake Unit Well No. 1

Location C/NW/SE Sec. 11 Twp. 31s Rge. 9 (E) (W) W

County Harper Total Depth 4435

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Clarke Oilfield Service Inc.

Address Chapin Bldg. Medicine Lodge, Ks License No. 583

Operation Completed: Hour 12:30 PM Day 20 Month 3 Year 1971

The above well was plugged as follows:

411 ft of 7 5/8 surface pipe cemented with 325 sacks. 4434 ft of 4 1/2  
long string cemented with 75 sacks. Top perf; 4382 ft. Plug back to  
3100 ft with 50 sacks cement. Perf. at 2876 ft. Sand back to 2862  
ft., 4 sacks cement with bailer. Pulled 2700 ft of 4 1/2. Set 10 ft  
rock bridge at 300 ft. Fill hole with 4 yds of redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: D. Russell Bihert  
Well Plugging Supervisor

DATE 3/22/71

INV. NO. 3431-W