

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued August 1, 1967.

Operator's Full Name E. K. Edmiston

Complete Address 425 First National Bank Bldg., Wichita, Kansas 67202

Lease Name COX "A" Well No. # 1

Location SW SE NW Sec. 9 Twp. 31 Rge. 9 (E) (W)W

County Harper Total Depth 4465'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company

Address Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 5:30 P.M. Day 14th Month August Year 1967

The above well was plugged as follows:

275' of 8 5/8" surface pipe, cemented with 150 sacks. 4465' of 4 1/2" long
string, cemented with 125 sacks. Top perforation 4452'. Bottom of the hole
was sanded to 4400', and cemented with 4 sacks, through the dump bailer, with
cement from 4400' to 4350'. 3430' of 4 1/2" long string was recovered from the
hole. Hole was filled with mud to 260', rock bridge from 260' to 250', and
cemented with 25 sacks, with cement from 250' to 175'. Hole was filled with
mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with
cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/16/67

INV. NO. 6148-W

Signed: Archie Elving
Well Plugging Supervisor