

State of Kansas



15-703-2000 4-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1961
10-5-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Frank Pfannenstiel of Leben Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling, Incorporated etal

Complete Address: 815 Wichita Plaza, Wichita, Kansas.

Lease Name: Lawrence Well No. 1

Location: CNE-NW Sec. 36 Twp. 20 Rge. (E)(W) 35

County Wichita Total Depth 5125 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

455'--8 5/8" Surface pipe, cement circulated with 350 Sx.
Dakota section from 675 to 910'.

Circulate hole with heavy mud. Pull DP to 950' and displace 100 Sx
cement thru DP. Pull DP to 450' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent