



15-203-0000-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
MAY 11 1966
5-11-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bob Sargent of Sargent's Csg. Pulling has this
date requested permission to plug the following described well:
Amarillo Oil Co.
Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Amarillo Oil Company,

Complete Address: Box #151, Amarillo, Texas.

Lease Name: Weisner Well No. 1

Location: CNW-SW Sec. 34 Twp. 20 Rge. (E) (W) 35

County Wichita Total Depth 5075 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

478'--8 5/8" Surface pipe, cement circulated.
4732'--4 1/2" Production casing cemented with 150 Sx. Top of
cement @ 3850'. Top perforations from 4523 to 4563.

Spot 15 Sx. cement on Bottom. Pull 4 1/2" to 660' and circulate

heavy gel mud. Pull 4 1/2" to 600' and displace 35 Sx. cement.

Pull 4 1/2", set bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

K. L. Nichols
Conservation Division Agent