

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1966

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: John Jennings & Rains & Williamson Oil Co.

Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Jacobs Well No. # 1

Location: C NW Sec. 6 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4480' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

228' of 8 5/8" surface pipe, cement circulated with 175 sacks.

Fill hole with drilling mud to 225', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to the base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving