

2 010133

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-077-20,393-00-00

SEC. 4, T. 31 S, R. 8 W/E

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name SANDERS Well # B-1

Operator: T.X.O. PROD CORP.

County Harper 144.98

Name & Address Wichita Kansas

Well Total Depth 4460 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 279

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B. J. TITAN License Number \_\_\_\_\_

Address MED. LODGE

Company to plug at: Hour: 10:00 AM Day: 27 Month: 3 Year: 19 86

Plugging proposal received from Jerry Collins

(company name) T. X. O Prod Corp (phone) \_\_\_\_\_

were: Pump 35 sbh to 4400. Then perforate at 310 & circulate cement to surface filling backside & 4 1/2 with cement

Plugging Proposal Received by Stan Marcotta  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 1:30 PM Day: 27 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT They pumped 35 sbh & three traps with one sbh hole & a plug to 4300 ft. Then they perforated at 310 ft & filled the 8 5/8 & 4 1/2 from there to surface with 50/50 pap mix with 6% gel. They pumped 70 sbh to fill the top

Remarks: Tricket # 284445 B. J. Titan  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I did not observe this plugging.

DATE APR 1 1986

RECEIVED  
STATE CORPORATION COMMISSION

MAR 3 1986

Warrn Kipatid  
(TECHNICIAN)

INV. NO. 13221 MAY 13 1986

CONSERVATION DIVISION  
Wichita, Kansas

RO