

11-21

2-040661

2/2
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-20420-00-60

E/2 SW NE, SECTION 12 TOWNSHIP 31 RANGE 9W

OPERATOR LICENSE # 5042 3300 FEET FROM S SECTION LINE
1650 FEET FROM E SECTION LINE

OPERATOR Edmiston Oil Company, Inc.
NAME & 125 N. Market, #1260
ADDRESS Wichita, KS 67202

RECEIVED
KANSAS CORPORATION COMMISS

DEC 3 1991

LEASE NAME: Muir #A-2

COUNTY: Harper
WELL TOTAL DEPTH: 4525' CONSERVATION DIVISION
WICHITA, KS

CONDUCTOR PIPE: " @ ' 147.06
SURFACE CASING: 8-5/8" @ 245'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing Pulling
ADDRESS: Box 347, Chase, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Monty

COMPANY NAME: Kelso Casing Pulling PHONE: _____

WERE: 4-1/2" @ 4524' - perfs 4415-21'; 4470-79' - 35 sx on
perfs - 30 sx 1470' - 30 sx 1000' - circ 300' to surf.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 1300 DAY: 21 MONTH: 11 YEAR: 1991

ACTUAL PLUGGING REPORT:
Perfs were plugged by pumping 35 sx common to 3900' -
SI 700# - 4-1/2" csg shot @ 3400' & pulled to 1483' &
30 sx cmt spotted - 4-1/2" csg pulled to 990' & 30 sx
cmt spotted - 4-1/2" csg pulled to 314' & cmt circ to
surface.

REMARKS: Allied Cmt #1764 60/40 4% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

Steve Van Gieson
Steve Van Gieson (AGENT)

DATE 12-9-91

INV. NO. 34048

FORM CP-2/3
REV. 3/90

aw