

11-26

2-040662 213  
RECEIVED  
KANSAS CORPORATION COMMISSION

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

DEC 3 1991

API NUMBER: 15-077-20395-00-00 CONSERVATION DIVISION  
WICHITA, KS

SE NW NE , SECTION 12 TOWNSHIP 31 RANGE 9W

OPERATOR LICENSE # 5042 4290 FEET FROM S SECTION LINE  
1650 FEET FROM E SECTION LINE

OPERATOR Edmiston Oil Company, Inc.  
NAME & 125 N. Market, #1260  
ADDRESS Wichita, KS 67202

LEASE NAME: Muir #A-1

COUNTY: Harper 146.60  
WELL TOTAL DEPTH: 4511'

CONDUCTOR PIPE: " @ '   
SURFACE CASING: 8-5/8" @ 247'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing Pulling  
ADDRESS: Box 347, Chase, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Monty

COMPANY NAME: Kelso Casing Pulling PHONE: \_\_\_\_\_

WERE: 4-1/2" @ 4560' - perms 4536-42'; 4431-35'; 4415-21' -  
sand to 4350' & 4 sx - 30 sx 1470' - 30 sx 1000' - circ  
300'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 1130 DAY: 26 MONTH: 11 YEAR: 1991

ACTUAL PLUGGING REPORT:  
Perfs were sanded back to 4350' & capped w/4 sx cmt -  
4-1/2" was shot loose from 3640' & pulled to 1472' &  
30 sx cmt spotted - 4-1/2" pulled to 1010' & 30 sx cmt  
spotted - 4-1/2" pulled to 422' & cmt circ to surf.

REMARKS: Allied Cmt #1768 60/40 poz 4% gel

I DID OBSERVE THIS PLUGGING.

Steve Van Gieson  
Steve Van Gieson (AGENT)

FORM CP-2/3  
REV. 3/90

INVOICED

DATE 12-9-91  
INV. NO. 34047

DW