

2-040772

7-20

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-077-20, ³³⁴318-0000
C W2 NW, SECTION 9 TOWNSHIP 31 RANGE 9W

OPERATOR LICENSE # 31289 3960 FEET FROM S SECTION LINE
4620 FEET FROM E SECTION LINE

OPERATOR NJRE OPERATING CO
NAME & 2400 BANK IV CNTR
ADDRESS 15 WEST 6TH STREET
TULSA OK 74119

LEASE NAME: COX C-1 145.11
COUNTY: HARPER
WELL TOTAL DEPTH: 4465' PB 2597'

PIPE: 4-1/2" @ 4452'

SURFACE CASING: 8-5/8" @ 257'

ABANDONED OIL WELL GAS WELL INPUT WELL SLD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARKE CORP
ADDRESS: MEDICINE LODGE KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: JEFF S.
COMPANY NAME: CLARKE CORP PHONE: _____

WERE: CIBP @ 2500' & 2 SX - 35 SX 1500' - 35 SX 950' - CIRC
275'-0' - PBDT 2597' - OH 4455-65' - CIBP 3450'
PERFS 2554-66'

PLUGGING PROPOSAL RECEIVED BY: STEVE VAN GIESON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 10:00 DAY: 20 MONTH: 7 YEAR: 1994

ACTUAL PLUGGING REPORT:
CIBP SET @ 2500' & CAPPED W/2 SX CMT - CSG SHOOT
LOOSE @ 2000' & PULLED TO 1494' & 35 SX CMT SPOTTED -
CSG PULLED TO 937' & 35 SX SPOTTED - CSG PULLED TO 310'
& CMT CIRC TO SURFACE


REMARKS: ALLIED CMT #6443 60/40 4%

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 9-8-94

INV. NO. 41141


Steve Van Gieson (AGENT)

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 06 1994

CONSERVATION DIVISION
WICHITA, KS
FORM CP-2/3
REV. 3/90

DW