

1 190854 9-22
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 135-24,012-00-00
60' S. of
W/2 SW SW, SEC. 12, T 16 S, R 23 ~~XX~~
600 feet from S section line
330 feet from W ~~X~~ section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3447
Operator: Ranken Energy Corporation
Name & Address: 601 N. Kelly, Ste. 103
Edmond, OK 73003-4855

Lease Name: Beyrle Well # 1-12
County: Ness 145.45
Well Total Depth: 4475 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWO Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor: Abercrombie RTD, Inc. License Number: 30684
Address: 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 11 a.m. Day: 22 Month: 9 Year: 19 97

Plugging proposal received from: Tony Martin
(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 1816' with 50 sx cement, 2nd plug at 1000' with 80 sx cement,
3rd plug at 650' with 40 sx cement, 4th plug at 230' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by: Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:15 p.m. Day: 22 Month: 9 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 1816' with 50 sx cement,
2nd plug at 1000' with 80 sx cement,
3rd plug at 650' with 40 sx cement,
4th plug at 230' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

9-30-97

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

Signed:  (TECHNICIAN)

DATE: 9-30-97
INV. NO. 49179
9-22