

1041129

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 007-20,506-00-00

NW SE SW, SEC. 27, T 30 S, R 11 W/8

990 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7963

Lease Name Thom Well # 27-14

Operator: Fancher Oil

County Barber 123.83

Name: Trinity Place

Well Total Depth 3810 feet

Address: 1801 Broadway #720

Conductor Pipe: Size feet

Denver, CO 80202

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10:45 a.m. Day: 12 Month: 12 Year: 19 95

Plugging proposal received from Darrell Musgrove

(company name) Bowers Drilling (phone) 316-886-5520

Work: 4 1/2" at 3809' w/100 sx cement, PBD 3779', Perfs at 3743-48'

1st plug sand back to 3690' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:30 a.m. Day: 12 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3690' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 400 psi.

Remarks: Used 65/35 Pozmix 6% gel by Allied. Recovered 2168' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION 12-14-1995 DEC 14 1995

CONSERVATION DIVISION Wichita, Kansas

INVOICED observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 1-8-96 INV. NO. 44440