

2 040167

No intent
old note

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-077-20944-00-06

SEC. 19, T 32 S, R 8 NE

4620 feet from N/4 section line

4620 feet from W/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5195

Lease Name Ferrel Well # 6

Operator Name & Address Rescure Venture

County Harger 123 34

Address 1501 Superior

Well Total Depth 3795 feet

Lincoln Nebraska
68521

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 270

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6850

Address Bx 176 Chase KS

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Norman Voth

(company name) Kelso Casing Pulling (phone) _____

were: 35 sx to 3600' (3500) - Circ. 50 sx gel @ 1500' thru 4 1/2'
Circ. 100 cement @ 300' thru 4 1/2'

4 1/2 3793

Perf 3752-55

FEB 21 1985

Plugging Proposal Received by Steve Van Guesor
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1340 Day: 8 Month: 2 Year: 19 85

ACTUAL PLUGGING REPORT Squeezed 35 sacks of cement in the 4 1/2" casing to 3500' by Sun Cementing Ticket # 206707 MX 1000 ST 700
2-4-85 - Shot 4 1/2" casing loose, and pulled to 1500 ft. Circulated 50 sacks of gel at 1500'. Pulled 4 1/2" casing to 300' and circulated 120 sacks of cement. Pulled remaining casing and filled hole to surface with cement. (1045)

Remarks: Sun Cementing # 206525
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 4-3-85
V. NO. 7531

WK

Signed Steve Van Guesor
(TECHNICIAN)

RO