

2 040126

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-077-20990-00-00

gelse, SEC. 19, T 32 S, R 8 10

375 feet from 03 section line

1150 feet from 08 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5303

Lease Name City Well # 4

Operator: Attica Gas Ventures

County Harper 121.91

Name & Address 123 N. Main

Well Total Depth 3751 feet

Attica Ks.

Conductor Pipe: Size _____ feet

John Eck.

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hause Well Service License Number _____

Address Attica Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Carl Durr

(company name) Attica Gas Venture (phone) _____

were: 50 sk on Bottom

3 Hull 6 Gel 100 sx Com 3% cc

5 1/2 3750

Perf. 3684-92 3706-10

Plugging Proposal Received by Stall Green
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1415 Day: 2 Month: 11 Year: 19 84

ACTUAL PLUGGING REPORT

A 50 sack Plug was pumped down the 5 1/2" casing and stopped at 3559', by Sun Cementing 11-1-84 at 1440, Ticket # 204351. Maximum Pressure 1400# and skurt in at 500#. The casing was pulled the nexted day. The Top was plugged with 3 sx of Hulls, 6 sx of gel and 100 sx of Com. Cement 3% cc. By

Remarks: Sun Cementing Ticket # 204352 MX OVER
(If additional description is necessary, use BACK of this form.)

I did did not) observe this plugging.

DATE 11-20-84

W

Signed Stall Green
(TECHNICIAN)

INV. NO. 4876

RC

There was not enough cement (1000x) to Plug the
the surface. The Plug was displaced 4.5 Barrels
of water, and then went back 11-6-84 and Redi-mix
the surface full. By Kingman Redi-mix