

11-2

2-040658

44  
L

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-077-20,902-00-00

SW, SECTION 19 TOWNSHIP 32 RANGE 8W

OPERATOR LICENSE # 5039

175 FEET FROM S SECTION LINE  
3290 FEET FROM E SECTION LINE

OPERATOR Attica Gas Ventures  
NAME & 123 N. Main  
ADDRESS Attica, KS 67009

LEASE NAME: Attica City #3

COUNTY: Harper 125.12

WELL TOTAL DEPTH: 3850' PB 3799'

CONDUCTOR PIPE: 13-3/8" @ 57'

SURFACE CASING: 8-5/8" @ 312'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SLD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Shawnee Well Service  
ADDRESS: Attica, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Carl Durr  
COMPANY NAME: Attica Gas Ventures PHONE: \_\_\_\_\_

WERE: PBTD 3799' - 5-1/2" @ 3846' - CIBP 3628' & 2 sx - 30  
sx @ 1400' - 30 sx @ 900' - circ 362' to surf - perfs  
3678-86', 3692-3702'.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( X ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 1745 DAY: 2 MONTH: 11 YEAR: 1991

ACTUAL PLUGGING REPORT:  
A CIBP was set at 3628' & capped w/2 sx cmt - 5-1/2"  
was shot loose from 2610' & pulled to 1407' where 30 sx  
cmt spotted - 5-1/2" pulled to 907' & 30 sx cmt spotted  
- 5-1/2" pulled to 366' & cmt circ to surface.  
recovered 2610'

REMARKS: B. J. Services #060208 common 3% cacl

**INVOICED**  
I DID OBSERVE THIS PLUGGING  
STATE CORPORATION COMMISSION

DATE 12-4-91 NOV 18 1991

Steve Van Gieson  
Steve Van Gieson (AGENT)

INV. NO. 33917  
CONSERVATION DIVISION  
WICHITA, KS

FORM CP-2/3  
REV. 3/90

DW