

11-5

2-040657

43
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-20,744-00-00

SE NE, SECTION 19 TOWNSHIP 32 RANGE 8W

OPERATOR LICENSE # 5039 3300 FEET FROM S SECTION LINE
660 FEET FROM E SECTION LINE

OPERATOR Attica Gas Ventures
NAME & 123 N. Main
ADDRESS Attica, KS 67009

LEASE NAME: Attica City #2

COUNTY: Harper

WELL TOTAL DEPTH: 3727' 121.12

CONDUCTOR PIPE: " @ '

SURFACE CASING: 8-5/8" @ 290'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Shawnee Well Service
ADDRESS: Attica, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Carl Durr
COMPANY NAME: Attica Gas Ventures PHONE: _____

WERE: OH 3684-3727' - 5-1/2" @ 3684' - CIBP 3634' & 2 sx -
30 sx 1400' - 30 sx 900' - circ 3440' to surf.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 1705 DAY: 5 MONTH: 11 YEAR: 1991

ACTUAL PLUGGING REPORT:
A CIBP was set at 3634' & capped w/2 sx cmt - 5-1/2"
was shot loose from 2200' & pulled to 1397' where 30 sx
cmt spotted - 5-1/2" pulled to 915' & 30 sx cmt spotted
- 5-1/2" pulled to 340' & cmt circ to surface.

REMARKS: B. J. [RECEIVED] #060307 common 2% cacl

DID YOU RESERVE THIS PLUGGING?
KANSAS CORPORATION COMMISSION

INVOICED

DATE 12-4-91 NOV 18 1991

INV. NO. 33916 CONSERVATION DIVISION
WICHITA, KS

Steve Van Gieson
Steve Van Gieson (AGENT)

FORM CP-2/3
REV. 3/90

DW