

2-7

2-040797

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 207B  
Wichita, Kansas 67202

15-077-00219-00-00

API NUMBER: 2/3/56

SW SW SW, SECTION 2 TOWNSHIP 31 RANGE 9W

OPERATOR LICENSE # 5003

330  
4950 FEET FROM S SECTION LINE  
FEET FROM E SECTION LINE

RECEIVED  
KANSAS CORPORATION COMMISSION

OPERATOR MCCOY PETROLEUM CORP  
NAME & 3017 N CYPRESS  
ADDRESS WICHITA KS 67226

MAR 09 1995

LEASE NAME: DORA MILLER #1 CONSERVATION DIVISION  
COUNTY: HARPER WICHITA KS  
WELL TOTAL DEPTH: 4530' 147.23

PIPE: 5-1/2" @ 4510'

SURFACE CASING: 8-5/8" @ 240'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SMD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: ALLIED CMT  
ADDRESS: \_\_\_\_\_ LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: JANA GREEN

COMPANY NAME: MCCOY PETRO CORP PHONE: 316-

WERE: PERFS 4461'-65' - SAND TO 4400' & 5 SX - PULL CSG -  
35 SX 1350' - 35 SX 900' - CIRC 300'

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 15:30 DAY: 7 MONTH: 2 YEAR: 1995

ACTUAL PLUGGING REPORT:

PERFS WERE COVERED W/SAND TO 4400' & CAPPED W/5 SX OF  
CMT - COULD ONLY GET 250' OF STRETCH ON 5-1/2" - LEFT  
5-1/2" IN HOLE - PERFED @ 1400' - PUMPED 35 SX -  
DISPLACED TO 1200' - SET CIBP @ 950' - PERFED @ 900' -  
WOULD NOT CIRC - PERFED 800' - PUMPED 35 SX CMT -  
DISPLACED TO 600' - SET CIBP @ 250' - PERFED 240' -  
CIRC CMT TO SURF

REMARKS: ALLIED 60/40 4% GEL 2% CACL

I DID OBSERVE THIS PLUGGING.

INVOICED

Steve Van Gieson  
Steve Van Gieson (AGENT)

DATE 3-10-95

INV. NO. 42347

FORM CP-2/3  
REV. 3/90

DW 2-7