

1 051918

4-13

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 135-23,871-0000
80' W of E/2 NE NE, SEC. 9, T 16 S, R 23 W/E

660 feet from NXK section line
410 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Smith "VV" Well # 1

Operator: Pickrell Drilling Company, Inc.

County Ness

Name & Address 110 N. Market, Ste. 205

Well Total Depth 4450 144.63 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 5/8 feet 225

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123

Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 13 Month: 4 Year: 19 95

Plugging proposal received from Doyle Folkerts

(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through bailer Anhydrite 1773-1811'

1st plug at 1810' with 50 sx cement, 2nd plug at 1050' with 80 sx cement,

3rd plug at 250' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6:16 a.m. Day: 13 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 1810' with 50 sx cement,

2nd plug at 1050' with 80 sx cement,

3rd plug at 250' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

4-20-95
APR 2 1995

INVOICED

additional description is necessary, use BACK of this form.)

DATE 4-28-95

Signed Richard M. Lacey (TECHNICIAN)

INV. NO. 42715