

To: 1 060794
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,460-10001 ³⁰¹ R

C NW SE, SEC. 9, T 16 S, R 23 W
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5501

Lease Name Beamer OWWO Well # 1

Operator: Raymond M. Goodin Trust
Name & Address 333 E. English, Suite 280
Wichita, KS 67202

County Ness 145.93
Well Total Depth 4490 Mississippi feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 339

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302
Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 7:00 am Day: 2 Month: February Year: 19 86

Plugging proposal received from Bill Ayres
(company name) Red Tiger (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1875
Elevation 2435

1st plug at the base of the Anhydrite with 60 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug at 360'. with 40 sx cement

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
Solid bridge

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:00 am Day: 2 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1875' with 60 sx cement, 2nd plug at 720' with 80 sx
cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug
at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15
sx cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 4 1986

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 50/50 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

FEB 6 1986

Signed Paul A. Luthie
(TECHNICIAN)

DATE _____

INV. NO. 12404

2-2