

1 090383

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,927-0000
2000' FNL, 2000' FWL
NW, SEC. 3, T 16 S, R 23 (W/R)

4320 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Curtis Well # 1

Operator: A. Scott Ritchie

County Ness 143.39

Name & Address 125 North Market, Suite 950

Well Total Depth 4412 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 4:00 pm Day: 16 Month: October Year: 1985

Plugging proposal received from Morris Shurfick

(company name) Murfin (phone) 316-267-3241

Elevation 2394 GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1758-96'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 pm Day: 16 Month: October Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 1800' with 50 sx cement, 2nd plug at 1110' with 80 sx

cement, 3rd plug at 330' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1985

10-28-85

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE OCT 29 1985

INV. NO. 10807

10-16

Signed R.B. Tarbutton
(TECHNICIAN) R.B.