

To: 1 071113
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,700-~~000~~ 92
C NE NE, SEC. 2, T. 16 S, R. 23 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 30444
Operator: Charter Production Company
Name: _____
Address 224 E. Douglas, Ste. 400
Wichita, KS 67202

4620 feet from S section line
660 feet from E section line
Lease Name Scott "A" Well # 1
County Ness 142.03
Well Total Depth 4370 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 7 p.m. Day: 15 Month: 10 Year: 19 92
Plugging proposal received from Randy Farr
(company name) Murfin Drilling Company, Inc. (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1674-1719'
1st plug at 1720' with 50 sx cement, 2nd plug at 1000' with 80 sx cement,
3rd plug at 330' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 8:30 p.m. Day: 15 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1720' with 50 sx cement,
2nd plug at 1000' with 80 sx cement,
3rd plug at 330' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1992
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
il (copy) / bill to observe this plugging.

DATE 10-27-92
INV. NO. 36613

Signed Dan Goodrow
(TECHNICIAN)