

To: 1 071138 12-30-
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,565-0000 15R
W/2 SW NE, SEC. 21, T 16 S, R 23 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9390
Operator: Schreiber Oil Company
Name & Address: P.O. Box 5
Beaver, KS 67517-0005

3300 feet from S section line
2310 feet from E section line
Lease Name Scherzinger Well # 3
County Ness
Well Total Depth 4453 14472 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:45 a.m. Day: 30 Month: 12 Year: 19 92

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

work: 5 1/2" at 4451' w/200 sx cement, Perfs at 4061-65, 4444-53'
1st plug sand back to 4000' and dump 5 sx cement on top of sand through bailer,
2nd plug pump through casing at 1000' with 50 sx cement,
3rd plug at 700' with 50 sx cement,
4th plug at 400' with 50 sx cement, 5th plug top off with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:45 p.m. Day: 30 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' and dumped 5 sx cement on top of sand through bailer,
Pumped through casing:
2nd plug at 1000' with 50 sx cement,
3rd plug at 700' with 50 sx cement,
4th plug at 400' with 50 sx cement,
5th plug topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Casing parted at 1150'.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 1-25-93
INV. NO. 37234

1-13-93
Signed Dan Goodrow (TECHNICIAN)
WICHITA, KANSAS