

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21866-00-00
Spot: CNWNW Sec/Twnshp/Rge: 21-16S-23W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: DIETTERICH B Well Number: 2
County: NESS Total Vertical Depth: 4467 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: P.O. BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: 8/45.18
Surface Casing: Size 8.625 feet: 362
Production: Size 5.5 feet: 4466 WITH 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/02/2002 1:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: RUN 2 3/8" TUBING TO 4400' & PUMP 40 SX CMT & 300# HULLS. AT 1900' PUMP 40 SX CMT THROUGH TUBING UP TO 1000' CIRCULATE CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/02/2002 5:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4464'. PERFS AT 4049-61, 4250-53, 4442-44, 4450-53'. DV TOOL @ 1824' WITH 390 SX CMT. CIRCULATED TO SURFACE. HOLES IN CASING FROM 2076-3096'. PUMP 40 SX CMT & 200# HULLS FOR BOTTOM PLUG. PUMPED 15 SX GEL TO 1900', THEN 40 SX CMT. PULLED TO 1000' & PUMP 75 SX CMT. CMT CIRCULATED. PULLED TUBING & TIED ONTO BACKSIDE. PRESSURED TO 500# RIGHT AWAY. TOPPED OFF CASING WITH 15 SX CMT. HOLE STAYED FULL.

RECEIVED
MAY 06 2002
5-6-02
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Michael J. Maier
(TECHNICIAN)

INVOICED MAY 03 2002
DATE 5-7-02
INV. NO. 2002061748 MP

FORM CP 25