

To: 1 071137 1-6
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-21,165-0000 16p
C NW NE, SEC. 21, T 16 S, R 23 W/E
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9390
Operator: Schreiber Oil Company
Name & Address: P.O. Box 5
Beaver, KS 67517-0005

Lease Name Scherzinger Well # 2
County Ness 145.60
Well Total Depth 4480 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 6 Month: 1 Year: 19 93

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4479' w/150 sx cement, Perfs at 4441-47'
1st plug sand back to 4390' and dump 5 sx cement on top of sand through bailer,
2nd plug spot through casing 50 sx cement at 1800',
3rd plug at 1000' with 80 sx cement,
4th plug at 330' with 50 sx cement, 5th plug top off with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 6 Month: 1 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug sanded back to 4390' and dumped 5 sx cement on top of sand through bailer,
Spotted through casing:
2nd plug at 1800' with 50 sx cement,
3rd plug at 1000' with 80 sx cement,
4th plug at 330' with 50 sx cement,
5th plug topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing. 1-13-93

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 1-25-93
INV. NO. 37239

Signed Dan Goodrow (TECHNICIAN)
WICHITA, KANSAS
JAN 13 1993
STATE CORPORATION COMMISSION