

KS
KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Edmiston Oil Co

Complete Address 405 1st Natl Bldg Wichita, KS

Lease Name Cox B Well No. 1

Location C E/2 E/2 SE Sec. 5 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4490

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Corporation

Address Box 187 Medicine Lodge, KS License No. 583

Operation Completed: Hour 1:00 PM Day 19 Month 9 Year 1974

The above well was plugged as follows:

275 ft 8 5/8 surface cement circulated. 4490 ft 4 1/2 long string
cemented with 125 sacks. Top perf. 4459 ft. Sand to 4415 ft, 4 sacks
cement with bailer. Pulled 3600 ft 4 1/2. Set 10 ft rock bridge at
360 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *Russell B. Burtin*
Well Plugging Supervisor

INVOICED

DATE 9/23/74
INV. NO. 9929-W