

KANSAS

df
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1967
10-5-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Leben Drilling, Incorporated et al,

Complete Address: 815 Wichita Plaza, Wichita, Kansas.

Lease Name Lawrence Well No. 1

Location CNE-NW Sec. 36 Twp. 20 Rge. (E) (W) 35

County Wichita Total Depth 5125

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: 815 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 9:00AM Day 1 Month 10 Year 1967

The Above well was plugged as follows:

455'--8 5/8" Surface pipe, cement circulated with 350 Sx.
Dakota section from 695' to 910'.

Circulated hole with heavy mud. Pulled DP to 990' and displaced 100Sx. cement plus
6% gel from 990' to 575'. Pulled DP to 450' and displaced 20 Sx. cement plug 6% gel
thru DP from 450' to 375'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*
Well Plugging Supervisor

DATE 10/9/67
INV. NO. 6455-4