

KANSAS
STATE CORPORATION COMMISSION

15-203-000 20-0000

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAY 11 1966
5-11-66
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Amarillo Oil Company.

Complete Address: Box # 151, Amarillo, Texas.

Lease Name Weisner Well No. 1

Location CNW-SW Sec. 34 Twp. 20 Rge. (E) (W) 35

County Wichita Total Depth 5075

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Sargent's Casing Pulling Service.

Address: Box #506, Liberal, Kansas. License No. 511

Operation Completed: Hour 3:00PM Day 9 Month 5 Year 1966

The Above well was plugged as follows:

478'--8 5/8" Surface pipe, cement circulated.
4752'--4 1/2" Production casing cemented with 150 Sx. Top of cement @ 3850'.
Top perforations from 4523' to 4565'.

Spotted 15 Sx. cement on bottom. Pressured up to 1200#. Left top of plug
@4269'. Pulled 4 1/2" to 650' and circulated heavy gel mud. (Used 6 Sx. fresh
gel). Pulled 4 1/2" to 600' and displaced 35 Sx. cement thru 4 1/2". Top of
plug @ 450'. Pulled 4 1/2", set rock bridge @ 35' and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5/11/66
INV. NO. 3200-w