

Handwritten initials and a small drawing of a person's head.

Form CP-3
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 28, 1967.

Operator's Full Name Mull Drilling Company, Inc.

Complete Address 1625 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name Culver Well No. # A-2

Location NE SE NW Sec. 4 Twp. 31 Rge. 8 (E) (W) W

County Harper Total Depth 4503'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling, Inc.

Address Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 3:00 P.M. Day 23rd Month August Year 1967

The above well was plugged as follows:

195' of 8 5/8" surface pipe, cemented with 175 sacks. 4497' of 5 1/2" long
string, cemented with 120 sacks. Plug back T.D. 4440'. Top perforation
4423'. Bottom of the hole was sanded to 4400', and cemented with 5 sacks,
through the dump bailer, with cement from 4400' to 4360'. 3100' of 5 1/2"
long string was recovered from the hole. Hole was filled with mud to 215',
rock bridge from 215' to 205', and cemented with 25 sacks, with cement
from 205' to 140'. Hole was filled with mud to 40', rock bridge from 40'
to 30', and cemented with 10 sacks, with cement from 30' to the base of
the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8-28-67
INV. NO. 67202-W