

State of Kansas



15-007-30277-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1966
11-14-1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Orr of Tom-Kat Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. ORR guarantees payment of the plugging fee.

Operator's full Name: Tom- Kat, Inc.

Complete Address: 1127 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Thom Well No. # 1

Location: C SW NE Sec. 27 Twp. 30 Rge. 11 (E)(W) W

County Barber Total Depth 3789' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. ORR was instructed to plug the well as follows:

258' of 8 5/8" surface pipe, cement circulated with 210 sacks. Fill
hole with drilling mud to 250', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of the cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent