

State of Kansas



15135-30222-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 9 1966  
8-9-66  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Williamson of Vaughan Drlg., Inc. has this date requested permission to plug the following described well:

Mr. Williamson guarantees payment of the plugging fee.

Operator's full Name: Vaughan Drilling Inc.

Complete Address: 1618 Wichita Plaza Wichita, Kansas

Lease Name: Hindergardt Well No. 1

Location: C NW NW Sec. 1 Twp. 16 Rge. 23 (E)(W) X

County Ness Total Depth 4360 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Williamson was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600 Ft.  
and displace 25 sc cement thru drill pipe. Heavy mud to 235 Ft. set  
cementing plug and displace 20 sc cement thru drill pipe. Heavy mud to  
40 Ft. set cementing plug, 1/3 sc hulls and 10 sc cement to base of  
celler. Plug rat hole with 2 sc cement.

Very truly yours,

L. J. Massey  
Conservation Division Agent