

State of Kansas



15-135-20117-01X10

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1968
CONSERVATION DIVISION
Wichita, Kansas
2-23-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Cooke of Imperial Oil Company has this
date requested permission to plug the following described well:

Mr. Cooke guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company

Complete Address: 780 Fourth Nat'l Bldg., Wichita, Ks.

Lease Name: Mischler Well No. 1

Location: C NE SE Sec. 29 Twp. 16 Rge. 23 (E)(W) X

County Ness Total Depth 4624 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cooke was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace
70 sc cement thru drill pipe. Heavy mud to 300' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Geo. F. Massey
Conservation Division Agent