

State of Kansas



15:135:36197-6000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1966
4-21-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Buehheister of John Farmer Dr. Co. has this date requested permission to plug the following described well:

Mr. Buehheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer Inc.

Complete Address: 370 Wichita Russell, Kansas

Lease Name: Schreiber Well No. 1

Location: NE-SW Sec. 22 Twp. 16 Rge. 23 (E)(W) X

County Ness Total Depth 4570 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buehheister was instructed to plug the well as follows:

Jett pits circulate hole with heavy mud, set cementing plug at 500 ft.,
and displace 20 sac cement thru drill pipe, heavy mud to 250' set
cementing plug and displace 20 sac cement thru drill pipe, heavy mud
to 40 ft., set cementing plug, 1/2 sac hulls and 10 sac cement, cementing
to base of cellar. Plug rat hole with two sac cement.

Very truly yours,

Leo Massey
Conservation Division Agent