

RECEIVED

OCT 16 2001

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-007-19016-0000 (identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Woolsey Petroleum Corp. KCC LICENSE # 5506
(owner/company name) (operator's)
ADDRESS 125 N. Market, Suite 1000 CITY Wichita
STATE KS ZIP CODE 67202 CONTACT PHONE # (620) 886-5606 Ext. 27

LEASE Palmer WELL# 1 SEC. 17 T. 32 R. 13 (East/West)

NE - SE SPOT LOCATION/QQQQ COUNTY Barber
1980 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)
660 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8 5/8" SET AT 230' CEMENTED WITH 200 SACKS
PRODUCTION CASING SIZE 5 1/2" SET AT 4598' CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4552'-4562', 4440'-4442', 4398'-4401',
4278'-4280', and 4007'-4009'
ELEVATION 1833' T.D. 4602' PBDT 4564' ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand back 50' above perforations to 3957'. Place 5 sx cmt on top of sand w/ dump bailer. Cut & lay down csg. Down 8 5/8" csg, pump 300# hulls, 10 sx gel, 100# hulls, plug, 150 sx cmt.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? no
If not explain why? none available

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Carl W. Durr PHONE# (620) 886-5606 Ext. 27

ADDRESS P.O. Box 168 City/State Medicine Lodge, KS 67104

PLUGGING CONTRACTOR Clarke Well Service KCC LICENSE # 5105
(company name) (contractor's)
ADDRESS Medicine Lodge, KS PHONE # (620) 886-5665

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 10-23-2001, 10:00 am

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT
DATE: 10/15/01 AUTHORIZED OPERATOR/AGENT: Carl W. Durr
(signature)

6/02

6/02