

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 1 Twp. 16S Rge. 23 (EX (W))

Location as "NE/CNW/SW" or footage from lines C NW NW

Lease Owner Vaughan Drilling, Inc.

Lease Name Hinnergardt Well No. 1

Office Address 1618 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 6 19 66

Application for plugging filed August 8 19 66

Application for plugging approved August 6 19 66

Plugging commenced August 6 19 66

Plugging completed August 6 19 66

Reason for abandonment of well or producing formation
No oil in commercial quantities.

If a producing well is abandoned, date of last production - - - 19 - - -

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas

Producing formation - - Depth to top - - Bottom - - Total Depth of Well 4360 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
				8 5/8"	241'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - - - feet to - - - feet for each plug set.

Filled hole with Rotary Mud to 600'. Set bottom plug
W/25 Sx. Cement. Middle Plug @ 241' W/1/2 Sx. Hulls & 20
Sx. Cement. Top plug @ 40' W/1/2 Sx. Hulls & 10 Sx. Cement.
25 Sx. Cement in Rat Hole.

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1966
8-10-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Vaughan Drilling, Inc.
Address 1618 Wichita Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Donald D. Vaughan, President

(Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald D. Vaughan
1618 Wichita Plaza, Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 8th day of August, 19 66

My commission expires 10-26-69
Marguerite Mayfield Notary Public.

VAUGHAN DRILLING, INC.
1618 Wichita Plaza, Wichita, Kansas

WELL LOG

COMPANY: Vaughan Drilling, Inc.
 CONTRACTOR: Vaughan Drilling, Inc.
 FARM: #1 Hinnergardt
 LOCATION: C NW NW Sec. 1-16S-23W
 Ness County, Kansas
 ELEVATION: 2325 Kelly Bushing
 SURFACE PIPE: 8 5/8" Cemented @ 241' W/175 Sx. Cement
 COMMENCED: 7-25-66
 COMPLETED: 8-6-66

<u>DEPTH</u>	<u>FORMATION</u>	<u>FORMATION TOPS (SAMPLE)</u>	
0 - 241	Shale	Anhydrite	1680
241 - 340	Black Shale	Heebner	3694 -1369
340 - 560	Shale & Sand Streaks	Lansing	3730 -1405
560 - 605	Sand & Shale Streaks	Base of Kansas City	4009 -1684
605 - 915	Shale & Sand	Pawnee Lime	4112 -1787
915 - 1530	Shale & Red Bed	Fort Scott	4204 -1879
1530 - 1680	Shale & Shells	Cherokee	4223 -1898
1680 - 1712	Anhydrite	Conglomerate	4290 -1965
1712 - 1920	Shale & Shells	Mississippi	4311 -1986
1920 - 2080	Lime & Shale	Rotary Total Depth	4360 -2035
2080 - 2320	Shale & Shell		
2320 - 2390	Lime		
2390 - 2665	Lime & Shale		
2665 - 2920	Lime		
2920 - 3405	Lime & Shale		
3405 - 3635	Lime, Shells & Chalk		
3635 - 4142	Lime		
4142 - 4210	Lime & Shale		
4210 - 4288	Lime		
4288 - 4360	Lime & Chert		

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1966

WICHITA COUNTY OFFICE
WICHITA, KANSAS

AFFIDAVIT

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Donald D. Vaughan, President of Vaughan Drilling, Inc., being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Donald D. Vaughan
 Donald D. Vaughan

Subscribed and sworn to before me this 8th day of August, 1966.

My Commission Expires: 10-26-69

Marguerite Mayfield
 Marguerite Mayfield, Notary Public