

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
214 No. Broadway
Wichita, Kansas

Ness County. Sec20 Twp.16 Rge. (E) 23 (W)

Location as "NE/CNW%SW%" or footage from lines C NE SE

Lease Owner Pickrell Drilling Company

Lease Name Dietterich Well No. 1

Office Address 705 4th National Bank Bldg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 3, 19 64

Application for plugging filed October 3, 19 64

Application for plugging approved October 3, 19 64

Plugging commenced October 3, 19 64

Plugging completed October 3, 19 64

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4585 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	271'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 275', set plug. Cemented with

25 sacks cement. Heavy mud to 45'. Set plug.

Cemented with 15 sacks cement to bottom of

cellar. Plugged rat hole with 2 sacks cement.

*Rec'd
10-8-64*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company

Address 705 4th National Bank Bldg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. SEBITS (employee of owner) of (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits

705 4th National Bank Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October, 19 64

Maxine Blackman
Maxine Blackman
Notary Public.

My commission expires June 21, 1966

ROTARY DRILLING LOG

15-135-00331-0000

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 9-22-64

Rotary Drilling Completed 10-3-64

LOCATION: C NE SE Section 20-16-23W, Ness County, Kansas
Dietterich No. 1

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (13 jts) 8 5/8" surface casing set at 271', cemented with 165 sacks cement. Circulated. Completed 4:30 P.M. September 22, 1964. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Surface Soil & Clay	<u>C. F. S.</u>
272	Shale & Shells	4310
940	Shale & Sand	4412
1180	Shale, Shells & Red Beds	4430
1200	Blaine	4485
1310	Shale & Shells	4491
1420	Sand	4500
1825	Red Bed, Shale & Shells	4510
1860	Anhydrite	4520
2260	Shale & Shells	4530
2620	Lime & Shale	4585
2964	Lime	
3618	Lime & Shale	<u>Slope Test</u>
3660	Sandy Lime & Shale	2500
3840	Lime & Shale	3000
4338	Lime	3500
4434	Lime & Shale	4000
4491	Lime, Shale & Sand	
4510	Lime & Shale	<u>S. L. M.</u>
4585	Mississippi - RTD	3695
		3902
		4354

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 8th day of October, 1964, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public