

RECEIVED  
OCT 22 1980  
PALOMINO  
PETROLEUM

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County, Sec. 30 Twp. 16S Rge. 23W E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
NE NE SE


Lease Owner Palomino Petroleum  
Lease Name Schoepfel Well No. #1  
Office Address 500 Insurance Bldg., Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed October 11, 1980 19  
Application for plugging filed October 11, 1980 19  
Application for plugging approved October 11, 1980 19  
Plugging commenced October 11, 1980 19  
Plugging completed October 11, 1980 19  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4580'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole plugged with 50-50 pozmix, 6% gel, as follows:  
70 sacks @ 700', 30 sacks @ 280', hulls and 10  
sacks @ 40', 5 sacks in rathole and mousehole.  
Plugging completed 8:15 a.m., October 11, 1980.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company

RECEIVED  
OCT 20 1980  
CONS. DIVISION  
WICHITA, KANSAS


STATE OF KANSAS COUNTY OF BARTON, ss.  
Charles W. Steincamp (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of October, 1980

Loneita Barry  
Loneita Barry Notary Public.

My commission expires 3-28-84.



RECEIVED

15-135-21879-0000

OCT22 1980

D R I L L E R S L O G

PALOMINO  
PETROLEUM

#1 Schoeppel

CASING RECORD:  
7 jts. new 23#  
8-5/8" surface  
casing

COMPANY: Palomino Petroleum  
CONTRACTOR: Strata Drilling Company  
COMMENCED: October 4, 1980  
COMPLETED: October 11, 1980

DESCRIPTION: NE NE SE  
Section 30-16S-23W  
Ness County, Kansas

TOTAL ROTARY  
DEPTH: 4580'

ELEVATION: 2507' KB

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>	
Surface soil, shale	0	295	Ran 282' new 23# 8-5/8" surface casing; set and cemented at 287' with 180 sacks common cement, 2% gel, 3% C.C. Cement circulated. Plug down at 8:15 p.m., October 4, 1980.	
Shale, sand, shells	295	1849		
Anhydrite	1849	1885		
Shale	1885	2025		
Lime and shale	2025	2730		
Lime	2730	3010		
Lime and shale	3010	4330		Ran one electric log, and one DST.
Lime	4330	4420		
Lime and shale	4420	4580		
				Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 700', 30 sacks @ 280', hulls and 10 sacks @ 40', 5 sacks in rathole and mouse-hole; plugging completed at 8:15 a.m., October 11, 1980.

STATE OF KANSAS )  
                  )ss  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.


STRATA DRILLING COMPANY

Charles W. Steincamp  
Charles W. Steincamp

Sworn to and subscribed before me this 21st day of October, 1980.

My appointment expires 3-28-84.

Loneita Barry  
Loneita Barry, Notary Public



NOV 20 1980  
Wichita, Kansas