


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plot

Ness County, Sec. 27 Twp. 16S Rge. (E) 23 (W)  
Location as "NE/CNW/SE" or footage from lines C SW SE  
Lease Owner O. A. Sutton  
Lease Name Cofer Well No. 1  
Office Address 800 Sutton Place, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 15 19 75  
Application for plugging filed December 15 19 75  
Application for plugging approved December 15 19 75  
Plugging commenced December 15 19 75  
Plugging completed December 15 19 75  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 4485  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	375'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug at 720' with 70 sacks; 2nd plug at 300' with 20 sacks;  
3rd plug at 40' with 10 sacks. Bridge rat hole with 2 sacks. Job complete at 4:30 p.m. 12-15-75. Job by Howco

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Gabbert-Jones, Inc.  
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK ss.  
Jack G. Paulsen (employee of owner) of (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack G. Paulsen  
800 Sutton Place, Wichita, Kansas 67202  
(Address)

Subscribed and sworn to before me this 29th day of December 19 75.  
My commission expires June 28, 1978.  
Jean S. Taylor Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 8 1976  
1-8-76  
CONSERVATION DIVISION  
Wichita, Kansas

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

Cofer #1  
 C-SW-SE Sec 27-16S-23W  
 Ness County Kansas

Commenced: 12-2-75

Completed: 12-15-75

OPERATOR: O. A. SUTTON

15-135-20950-0006

Depth		Formation	Remarks
From	to		
0	379	Surface Clay-Sand	Ran 9 jts of used 8 5/8" csg set @ 375' Cemented @/250 sks Common 2% Gel - 3% CC PD @ 4:15 a.m. 12-3-75
379	755	Clay-Sand	
755	1140	Shale-Sand	
1140	1230	Shale	
1230	1505	Sand	
1505	1799	Shale-Shells	
1799	1831	Anhy	
1831	1920	Shale-Redbed	
1920	2480	Shale	
2480	2535	Lime-Shale	
2535	2690	Shale-Lime	
2690	3975	Lime-Shale	
3975	4485	Lime	
	4485 - TD		DRY & ABANDONED

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled C-SW-SW Sec 27-16S-23W, Ness County Kansas to the best of my knowledge and belief.

*James S. Sutton II*  
 JAMES S. SUTTON II

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 18th day of December, 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

*Elizabeth J. Edwards*  
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission Expires: February 6, 1979.



RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 8 1976  
 CONSERVATION DIVISION  
 Wichita, Kansas