

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 1583-23122-00-00

LEASE NAME Klitzke

WELL NUMBER 2

4040 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 35 TWP. 16 S RGE. 23 (E) or (W)

COUNTY Ness

Date Well Completed 6/22/87

Plugging Commenced 12/12/02

Plugging Completed 12/12/02

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

REC 10
12-18-02

LEASE OPERATOR American Warrior, Inc.

ADDRESS P.O. Box 399, Garden City, KS 67846

PHONE# (785) 308-2270 OPERATORS LICENSE NO. 4058

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/12/02 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? None

Producing Formation NA Depth to Top _____ Bottom _____ T.D. 1740'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cedar Hill	water	1185	1394	8 5/8	249'	None
				5 1/2	1729'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Mixed 125 sacks of Swift Lite with 300# of hulls, pumped 37.2 bbls @ 1000 psi max, mixed 20 sks Swift Lite and pumped 6 bbls down 8 5/8 braden head max pressure 500 psi, mixed 10 sacks Swift Lite, 3 bbls and topped off 5 1/2 casing. Job complete.

Name of Plugging Contractor Swift Services, Inc. License No. 32382

Address N Highway 283, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior, Inc.

STATE OF Kansas COUNTY OF Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) o
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed the
the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 210 Avenue A, Bazine, KS 67516

SUBSCRIBED AND SWORN TO before me this 16th day of December, 19 2002

Bernice Moore
Notary Public

My Commission Expires: 2/17/06



Form CP-4
Revised 03-02

CR